Proposed Griffin Hospital CHP



Exterior Finish Schedule

1	MTL. PRIVACY FENCING SYSTEM W/ INFILL SLATS BY FENCE TRAC OR EQUAL - (4" SQ. POSTS X 11 GA. W/ BOT./ TOP & POST MOUNT TRAC) - MTL. COMPONENTS TO BE STD. 'DARK BRONZE' FINISH - INFILL SLAT TO BE PVC ULTRA-TECH 'TROPICAL TEAK'
2	3 SIDED SCREEN FOR ROOF TOP MECH. UNIT - W/ POSTS & COMPOSITE WOOD SLATS 'PERUVIAN TEAK' BY TECHWOOD OR EQUAL - FASTENED TO FRAMING AT 24" OC
3	DUCT WORK FINISHED WITH KRYLON HIGH HEAT METALLIC BROWN

Note: The architectural fencing (1) and roof screening (2) are selected to match the model and finish of that utilized on the newly constructed MRI building annex adjacent to the CHP installation.

RECEIVED
By Marc J Garofalo MPA, MMC, MCTC at 3:42 pm, Jun 08, 2026

Seymore St. View



RECEIVED
By Marc J Garofalo MPA, MMC, MCTC at 3:42 pm, Jun 08, 2026